

RESULTS OF ELECTRON CYCLOTRON HEATING AND CURRENT DRIVE SYSTEM OPERATION IN THE INTEGRATED COMMISSIONING PHASE ON JT-60SA


H. Yamazaki, M. Terakado, M. Sawahata, S. Hiranai, F. Sato, N. Toida, J. Hinata, T. Ishii,
K. Asakura, H. Sugiyama, K. Ishita, T. Shinya, R. Ikeda, T. Kobayashi and K. Kajiwara

National Institutes for Quantum Science and Technology (QST)

Multi-frequency ECRH system has constructed & operated on JT-60SA



Scenario5

$B_t = 1.7$ T, **110 GHz**




Scenario2

$B_t = 2.25$ T, **82/138 GHz**




The multi-frequency gyrotron expands experimental flexibility

- Two ECRH systems for the integrated commissioning phase






		JT-60U components	
		Unit#1	Unit#2
Gyrotron	Frequency	110 GHz	82/110/138 GHz
	Output power	1 MW	1 MW
	Pulse duration	5s	110/138 GHz: 5 s 82 GHz: 1s
Transmission line	WG	φ 31.75 mm	φ 60.3 mm
	Total length	95 m	105 m
	No. of MBs	15	15
	Transmission efficiency (calc.)	66% (74%)	79%/85%/84% (80%/83%/83%)

(a) Gyrotron output power [kW]



(b) Injection pulse width




to 1 MW / 1 s

& 82 GHz/1 MW

Unit 1 (110 GHz) from the first

- First plasma was achieved by ECRH injection with 110 GHz/1 MW & 82 GHz/1 MW
- 1.5 MW / ~1 s injection was also achieved.

Demonstration of 1.5 MW operation by single gyrotron




Electron beam power: $84.7 \text{ kV} \times 53.1 \text{ A} = 4498 \text{ kW}$
 Output power (calorimetry measured): 1550 kW
Oscillation efficiency: 34.5%

❑ Successfully achieved ~1 s of injection before stopping due to the arc signal interlock at the Torus window.

❑ The surface temperature of the waveguide in the MB closest to the launcher increased by 1.1 degrees, equivalent to a heat load of 16.7 kW/m^2

❑ This heat load is lower than the maximum heat load considered in the TL design, suggesting the potential for future high-power operation with 1.5 MW


Unit2 Gyrotron waveform



Unit1	Number of pulses	Failed	Success [%]
Plasma experiment sequence	340	34	90.0%
110 GHz < 1 s incl. wall cleaning	178	19	89.3%
≥ 1 s	162	15	90.7%


Unit2	Number of pulses	Failed	Success [%]
Plasma experiment sequence	350	34	90.3%
82 GHz < 1 s incl. wall cleaning	235	6	97.4%
110 GHz < 1 s incl. wall cleaning	58	15	74.1%
≥ 1 s width	57	13	77.2%
138 GHz	0	0	0.0%

Causes of Pulse Failure and Pulse Width



Progress of the TL conditioning

925 injection to v.v. from 6/26-6/30 for Unit2



- ❑ The median time of shots halted due to Torus window arc is 2 s and 1.1 s
- ❑ A conditioning operation of up to 1 MW/1 s prior to the plasma experiment is useful for suppressing Torus window arc occurring within 1 s.
- ❑ Other factors are "uncertain events" that are independent of the conditioning results.
- ❑ Note that for Unit 1, the cause is considered to be mode deviation resulting from a reduction in beam current (as discussed in the poster).




(Phased construction of JT-60SA ECRH system)

- Multi-frequency (82/110/138 GHz) ECRH system will be upgraded in three phase:
2 Units (I.C. phase) → 4 Units (init.R.P.) → 9 Units (integrated research phase)
- Transmission line (TL) development for initial research phase (4 units) is necessary.
- Demonstration of the TL has been conducted in the integrated commissioning phase

Integrated Commissioning Phase

Initial Research Phase

Integrated Research Phase



□ Determined transmission line layout for initial research phase


Unit1/Unit2: Transmission efficiency >85%

- total length of ~60 m
- 9 miter-bends including polarizers
- Connected on **P11-UO** launcher

Unit3/Unit4: Transmission efficiency >80%

- Total length of ~115 m
- 10 miter-bends including polarizers
- Connected to **P8-UO** launcher

		loss	Transmission efficiency	Target
P11 Unit1/2	82 GHz	10%	90%	85%
	110 GHz	9%	91%	
	138 GHz	9%	91%	
P8 Unit3/4	82 GHz	13%	87%	80%
	110 GHz	12%	88%	
	138 GHz	13%	87%	



Design target of 3 MW (75% efficiency x 4 units) of tokamak injection power can be achievable

ECRF system installation

- High transmission efficiencies of 80/82/84% at 3 operating frequencies of 82/110/138 GHz were achieved by large-diameter corrugated waveguide.

Results of RF operation

- The ECRF was used in almost all plasma experiments (including ECWC), with an average reliability of 90%.
- Units 1 (110 GHz) and 2 (82 GHz/110 GHz) were successfully injected with up to 1 MW/1 s from the first day of the experiment, contributing to the achievement of first plasma.
- Conditioning before the plasma experiment was helpful in preventing injection failures due to Torus window arc event.

Layout design for next initial research phase TLs

- We designed the 4 units of ECRH systems for the next phase and target transmission efficiency (>85%) is expected to be achieved.